

Addendum #02

Project: Fort Harrison Collection System Capacity Improvements – Phase I
For: City of Lawrence
To: All Bidders and Plan Holders
Engineer: Clark Dietz, Inc.
Date: May 31, 2023

The following is an addition to, clarification of, and/or modification of the Contract Documents for the Fort Harrison Collection System Capacity Improvements – Phase I. This Addendum shall become part of the Contract Documents. Acknowledge the receipt of this Addendum in the space provided on the Bid Form (Page 00 41 43-1) *Article 3, 3.01, A*.

Item No. 1 **Question:** How high can the wet well level be allowed to rise without creating backups into an upstream property or overflowing out the top of manholes?

Response: Lift Station 20 can be off for up to 6 hours or until the water level in the wet well is within 20 feet of the top of the structure, whichever happens first. The maximum fill elevation is 847.83 feet.

Item No. 2 **Question:** At the upstream end of the new sanitary sewer, what is the invert of the pipe connection to the existing manhole on Melner Drive?

Response: The new 10" sanitary sewer will connect to the existing manhole at an invert of 855.06 feet, on the south side of the manhole.